

FROM: ANTINOZZI ASSOCIATES
271 FAIRFIELD AVENUE
BRIDGEPORT, CT 06604

TO: ALL BIDDERS

RE: JOB NO. 14047
TOWN OF TRUMBULL
DPW FUELING STATION CANOPY
NEW ROOFING SYSTEM
366 CHURCH HILL RD., TRUMBULL, CT

SUBJECT: ADDENDUM NO. 1

DATE: OCTOBER 27, 2014

This Addendum shall be part of the Contract Documents for the referenced Bid. The Addendum is to acknowledge by the bidder on the Bid Form.

The following ADDENDUM is issued to clarify items appearing either in the specifications or on the Drawings, said items having been called to the attention of the Architect by one or more of the Contractors estimating the work:

The Specifications and / or drawings are amended as follows:

1. GENERAL – CLARIFICATIONS

- A. Clarification – New roof drain piping to be CPVC Schedule 40.
- B. Clarification – Relocate existing electrical wiring located on existing steel beams as required to install new metal deck.
- C. Clarification – Welding will not be allowed on the job site. In lieu of welding, the new metal decking shall be fastened to the supporting steel using powder actuated deck fasteners as manufactured by Hilti or approved equal, spaced 12” on center. Side lap screws and spacing shall remain as originally specified. The new structural steel shall be fastened to existing structural steel members using 5/8” diameter bolts spaced 16” on center. All new holes shall be magnetic drilled as required.

END OF ADDENDUM NO. 1