

## ADDENDUM NO. 3

### 2.1 Bid Form

- a. **Clarification:** It is the intent & scope of the project to provide New Heat Pump Systems for all Living Units in the Stern Village Campus.
- b. **Base Bid shall be for Units 1 through 54 and 65 through 186 inclusive (174 Living Units).**
- c. **Alternate No. 02 shall be for Units 55 through 64 (12 Living Units).**

### 2.2 Thermostats

- a. **Delete:** Integrating of existing electric baseboard line voltage thermostats to new Heat Pump & Air Conditioning units.
- b. Existing line voltage baseboard thermostats shall remain as is. Contractor shall report to the Trumbull Housing Authority Maintenance all no functioning existing line voltage electrical baseboard thermostats.
- c. New Living Unit Heat Pumps shall be furnished with one handle held remote control thermostat.

### 2.3 Transfer Grilles

- a. **Clarification:** Furnish & install sheet metal sleeves for all through wall transfer grilles.

### 2.4 Exterior Disconnect Switches

- a. **Delete:** Fused disconnect switches.
- b. **Add:** Non-Fused disconnect exterior switch at each condenser.

### 2.5 Interior Water Level Sensor

- a. **Add:** All interior new Air Handling Units shall be equipped with Water Level Sensor Option.

### 2.6 Exterior Service Outlet

- a. **Add:** one (1) Exterior GFI Weather Resistant duplex service outlet with gasket cover per building. Locate outlet as directed by Trumbull Housing Authority Maintenance in near proximity of one exterior condenser.

### 2.6 Addendum Numbering

- a. **Clarification:** Wiles Architects Addendum No. 1 shall be Town of Trumbull Purchasing Department Addendum No. 2.

**Attachments: NONE**

**End Addendum No.3**