

ADDENDUM NO. 2

TO

TOWN OF TRUMBULL, CONNECTICUT

BIDDING AND CONTRACT REQUIREMENTS AND SPECIFICATIONS

FOR

TOWN WIDE PIPE LINING

BID #6251

June 22, 2017

**PREPARED BY:
WRIGHT-PIERCE
169 Main Street
700 Plaza Middlesex
Middletown, CT 06457
Tel.860-343-8297
Fax-860-343-9504**

ADDENDUM NO. 2

TOWN OF TRUMBULL, CONNECTICUT
BIDDING AND CONTRACT REQUIREMENTS AND SPECIFICATIONS
FOR
TOWN WIDE PIPE LINING

This addendum amends and/or supplements the Bid Documents as indicated below. Only these items alter the Bid Documents; any verbal discussions or responses are hereby declared null and void. The Bidder shall indicate the receipt of all previously issued Addenda on the Proposal Form.

CLARIFICATIONS

1. Sealed bids for the Town Wide Pipe Lining Project will be received by the Town of Trumbull at the office of the Purchasing Agent, 5866 Main Street, Trumbull, CT, until 2:00 PM, local time, June 27th, 2017.
2. Attention is drawn to the fact that the Contractor is responsible for the cost of all water used during the project. General Conditions 6.03A states the following: “Unless otherwise specified in the Contract Documents, Contractor shall provide and assume full responsibility for all services, materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, temporary facilities, and all other facilities and incidentals necessary for the performance, testing, start up, and completion of the Work.” As stated in Section 01010, Summary of Work, 3.9C: “Although the Contractor is responsible for the cost of water used on the project, in Accordance with Part 6.03 of the General Conditions, the Town will provide a location to obtain water at the Highway Department Garage.”

SPECIFICATIONS

1. Section 02756, Storm Drain Pipe Lining, 3G: **ADD** the following to the end of the Section: “Cure water shall be cooled to below 100 degrees Fahrenheit prior to being discharged to the sanitary sewer. Cure water shall be free from spilled resin. Contractor shall take care to minimize effect of odors.”

QUESTIONS AND ANSWERS

I. Questions received via E-mail

Insituform Technologies, LLC (received June 20th, 2017)

1. Q: Will water be available to the GC free of charge?

A: No, the Contractor is responsible for the cost of all water used during the project. Please see Clarification No.2 above for additional information.

2. Q: Will steam installations for CIPP be allowed for ALL sizes? FYI – Insituform lines pipelines up to 72” with steam

A: Section 02756, Storm Drain Pipe Lining, 3F states that: “Steam curing shall only be allowed for pipe sizes of 18-inch diameter or smaller, unless written permission from the Engineer is granted.” This provision is to ensure that the pipes are cured properly and recognizes that as pipes increase in size it becomes more difficult for the top and bottom of the pipe to cure properly using steam. If a Contractor can provide a means of measuring and ensuring the liner temperature and for the full length and area of the pipe, then steam installations may be approved.

3. Q: Will the Town accept the grit accumulated from the cleaning operation?

A: Yes, The Town will accept the grit accumulated from the cleaning operations. The Contractor will coordinate with the Town during construction and will dispose of grit at the Department of Public Works location at Indian Ledge Park.

4. Q: Can cure water be pumped into the adjacent sewer line for disposal?

A: Please see the Specifications Section above in this Addendum for answer this this question.