

FROM: ANTINOZZI ASSOCIATES
271 FAIRFIELD AVENUE
BRIDGEPORT, CT 06604

TO: ALL BIDDERS

RE: JOB NO. 19050
TOWN OF TRUMBULL
EMERGENCY MEDICAL SERVICES BUILDING
ROOF REPLACEMENT
250 MIDDLEBROOKS AVE., TRUMBULL, CT

SUBJECT: ADDENDUM NO. 1

DATE: OCTOBER 14, 2019

This Addendum shall be part of the Contract Documents for the referenced Bid. The Addendum is to acknowledge by the bidder on the Bid Form.

The following ADDENDUM is issued to clarify items appearing either in the specifications or on the Drawings, said items having been called to the attention of the Architect by one or more of the Contractors estimating the work:

The Specifications and / or drawings are amended as follows:

1. SPECIFICATIONS – SECTION 024119 SELECTIVE DEMOLITION

A. Clarification regarding Asbestos Containing Materials: Roofing materials have been tested and results concluded that the base flashings and flashing cement do contain asbestos, however the roofing does not. All Asbestos Containing Materials shall be removed and disposed of in accordance with all local and state regulations. Refer to attached test report.

2. SPECIFICATIONS – SECTION 075310 FULLY ADHERED EPDM ROOFING

A. Part 2.01-A – Add the following: Provide 1/4" DensDeck Prime cover board throughout entire roof area.

END OF ADDENDUM NO. 1



Please Reply To:

AmeriSci New York

117 EAST 30TH ST.

NEW YORK, NY 10016

TEL: (212) 679-8600 • FAX: (212) 679-3114

FACSIMILE TELECOPY TRANSMISSION

To: Robert Brown

Hygenix, Inc.

Fax #:

Email: rbrown@hygenix.com

From: John P. Koubiadis

219102396

Subject: PLM 48 hour Results

Client Project: Antinozzi Assoc.; EMS Building -
250 Middle Brooks Ave, Trumbull,
CT 06611

Date: Saturday, October 12, 2019

Time: 15:32:15

Comments:

Number of Pages:

(including cover sheet)

CONFIDENTIALITY NOTICE: Unless otherwise indicated, the information contained in this communication is confidential information intended for use of the individual named above. If the reader of this communication is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is prohibited. If you have received this communication in error, please immediately notify the sender by telephone and return the original message to the above address via the US Postal Service at our expense. Samples are disposed of in 60 days or unless otherwise instructed by the protocol or special instructions in writing. Thank you.

Certified Analysis Service 24 Hours A Day • 7 Days A Week Competitive Prices
visit our web site - www.amerisci.com

Boston • Los Angeles • New York • Richmond



AmeriSci New York

117 EAST 30TH ST.
NEW YORK, NY 10016
TEL: (212) 679-8600 • FAX: (212) 679-3114

PLM Bulk Asbestos Report

Hygenix, Inc.
Attn: Robert Brown
49 Woodside Street
Stamford, CT 06902

Date Received 10/11/19 **AmeriSci Job #** 219102396
Date Examined 10/12/19 **P.O. #**
Page 1 **of** 1

RE: Antinozzi Assoc.; EMS Building - 250 Middle Brooks Ave,
Trumbull, CT 06611

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
1	219102396-01	Yes	20 % ¹ (by CVES) by John P. Koubiadis on 10/12/19
	Location: Base Flashing		
			Analyst Description: Black, Heterogeneous, Fibrous, Bulk Material Asbestos Types: Chrysotile 20.0 % Other Material: Cellulose 20 %, Non-fibrous 60 %
2	219102396-02	Yes	10 % (by CVES) by John P. Koubiadis on 10/12/19
	Location: Flashing Cement		
			Analyst Description: Black, Heterogeneous, Fibrous, Bulk Material Asbestos Types: Chrysotile 10.0 % Other Material: Cellulose 10 %, Non-fibrous 80 %
3	219102396-03	No	NAD (by CVES) by John P. Koubiadis on 10/12/19
	Location: Roofing		
			Analyst Description: Black, Heterogeneous, Fibrous, Bulk Material Asbestos Types: Other Material: Cellulose 25 %, Non-fibrous 75 %

Reporting Notes:

(1) This job was - Analyzed using Olympus BH-2 Pol Scope S/N 223705

Analyzed by: John P. Koubiadis

*NAD/NSD = no asbestos detected; NA = not analyzed; NA/PS = not analyzed/positive stop, (SOF-V) = Sprayed On Fireproofing containing Vermiculite; (SM-V) = Surfacing Material containing Vermiculite; PLM Bulk Asbestos Analysis by Appd E to Subpt E, 40 CFR 763 (NVLAP 200546-0), ELAP PLM Method 198.1 for NY friable samples, which includes the identification and quantitation of vermiculite or 198.6 for NOB samples or EPA 400 pt ct by Appd E to Subpt E, 40 CFR 763 (NY ELAP Lab 11480); Note:PLM is not consistently reliable in detecting asbestos in floor coverings and similar non-friable organically bound materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non asbestos-containing in NY State (also see EPA Advisory for floor tile, FR 59,146,38970,8/1/94) National Institute of Standards and Technology Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the lab. This PLM report relates ONLY to the items tested. AIHA-LAP, LLC Lab ID 102843, RI Cert AAL-094, CT Cert PH-0186, Mass Cert AA000054.

Reviewed By:

END OF REPORT

CHAIN OF CUSTODY FORM

CLIENT: ANTINORI ASSOC.
ADDRESS: 271 FAIRFIELD AVE.
BRIDGEPORT, CT 06604

DATE RECEIVED: 10/10/19
EMAIL: PLISI@ANTINOZZI.COM

SAMPLE SITE: EMS BUILDING
250 MIDDLE BROOKS AVE.
TRUMBULL, CT 06611

SAMPLE TYPE:	ROOFING ITEMS
COLLECTED BY:	BEACON REPS
DATE COLLECTED:	7-25-19
TURNAROUND:	ASAP - 2 DAYS

Email Reports to: rbrown@hygenix.com

enriched By: PAUL L 151
Date: 10-9-19

Received By: Mike Barnhill
Date: 10/10/19

M. Spence 10/11/19 11:53